

FLOOR PLAN GENERAL NOTES

- A. BOLLARDS ARE TO BE LOCATED WITHIN THE BUILDING TO PROTECT EXPOSED ELECTRICAL PANELS, ELECTRICAL GEAR, ROOF DRAIN PIPING, WATER LINES, GAS LINES, AND SPRINKLER TEST DRAIN PIPING WITHIN 8' OF WAREHOUSE FLOOR -
- PROVIDE REPLACEABLE YELLOW SLEEVE. B. PROVIDE BARRIER RAILS TO PROTECT EXPOSED FIRE SPRINKLER RISER - PAINT SAFETY YELLOW. C. PROVIDE 2"X2"X48" HIGH STAINLESS STEEL CORNER GUARDS
- (TYP.) AT ALL EXPOSED CORNERS, ADHERE TO WALL (NO D. PROVIDE SEALANT WHERE EDGE OF TILE ABUTS GYPSUM.
- OPENINGS AND CONTROL JOINT DETAILS. GC TO DETERMINE CONSTRUCTION METHODOLOGY. F. REFER TO DETAIL 2E/A11.1 FOR TYPICAL CHAIR RAIL DETAIL. G. REFER TO SHEET A11.2 FOR FLOOR TRANSITION DETAILS 4A,

4B, 4C, 5A, 5B, AND 5C.

REFER TO DETAIL 21/A8.2B FOR TYPICAL METAL STUD

PANEL AS REQUIRED.

OF ROOM. MITER CORNERS OF WALL JOGS.

- 1 WALK OFF CARPET TO FILL ENTIRE WIDTH & LENGTH OF VESTIBULE (SEE FINISH SCHEDULE). 2 MEDICAL CURTAIN - MEDICAL SUPPLIES & EQUIPMENT COMPANY (OR APPROVED EQUAL) (PH) 877-706-4480
- 100% POLYESTER FABRIC, 12OZ., ANTI-MICROBIAL TREATED, 5FT. STRAIGHT CUBICLE TRACK. 3 PROVIDE 1 1/2" x 1 1/2" PREFINISHED BENT-LEG METAL (22 GA.) ANGLE FULL HEIGHT OF PARTITION. (WHITE)
- ATTACH TO CONCRETE PANELS ONLY. SEE DETAIL 3C/A3.3 4 METAL DETECTION EQUIPMENT PROVIDED BY TENANT. CONTRACTOR TO COORDINATE & PROVIDE ELECTRICAL EQUIPMENT.
- 5 METAL LOCKERS TO BE FURNISHED BY TENANT OR TENANT'S VENDOR AND INSTALLED BY GC WHERE INDICATED ON PLAN. PROVIDE 5% ADA COMPLIANT LOCKERS. ADA COMPLIANT LOCKERS MAX. HEIGHT 46" AND ALL OPERABLE CONTROLS BETWEEN 15"-46" AFF. 6 VENDING EQUIPMENT BY TENANT (SEE ELECTRICAL SHEETS).
- 7 2"x2"x48" HIGH STAINLESS STEEL CORNER GUARD (TYP.), PROVIDE AT ALL EXPOSED CORNERS, ADHERE TO WALL (NO SCREWS)
- 8 ACCESSIBLE SPEEDLANE TURNSTILE BARRIER PROVIDED BY TENANT. CONTRACTOR TO INSTALL, COORDINATE & PROVIDE ELECTRICAL POWER AS REQUIRED. 9 HOLD FRAMING TIGHT TO FACE OF COLUMN AND/OR INTERIOR ROOF DRAIN. PROVIDE CLEAN OUT ACCESS

13 WOOD CHAIR RAIL - TOP OF RAIL AT 2'-9" A.F.F. CONTINUE CHAIR RAIL FOR ENTIRE LENGTH OF WALL THIS SIDE

- 10 ROOF & OVERFLOW DRAIN LEADER SEE DETAIL 5B/A9.6. 11 PROVIDE 8"W x 12"L OPENING IN COUNTERTOP. CENTER OPENING BETWEEN SINKS & FRONT TO BACK. 12 LINE OF 22" DIA. x 28" HIGH x 32 GAL. TRASH CONTAINER WITHOUT LID BELOW COUNTER. CONTAINER BY
- - 14 LINE OF TENANT PROVIDED & INSTALLED, MANUALLY OPERATED PULL-DOWN PROJECTOR SCREEN ABOVE. 15 LINE OF TENANT PROVIDED & INSTALLED PROJECTOR ABOVE. GC TO PROVIDE (4) 12GA. TIE WIRES FROM ROOF STRUCTURE DOWN TO SUSP. CEILING FOR TENANT PROVIDED PROJECTOR CEILING MOUNT. PROJECTOR &

MOUNT TO BE SUPPLIED & INSTALLED BY A/V CONTRACTOR (N.I.C.) (SEE ADJUSTABLE SUSPENDED CEILING

- CHANNEL KIT #ELPMBP01 BY PEERLESS MOUNTS FOR REQUIREMENTS. 800.729.0307). 16 LOCATION OF WALL OR CEILING MOUNTED TELEVISION MONITOR ABOVE, G.C. TO PROVIDE BLOCKING.
- MONITOR PROVIDED AND INSTALLED BY TENANT. G.C. TO COORDINATE ALL ROOF PENETRATIONS FOR SATELLITE CABLING WITH THE ROOFING CONTRACTOR. (SEE ELECTRICAL AND IT/AV SHEETS) LINE OF RECESSED TV MONITOR PROVIDED & INSTALLED BY TENANT. GC TO PROVIDE BLOCKING FOR BRACKET SUPPORT & ELECTRICAL & DATA OUTLETS FOR EACH MONITOR. VERIFY & COORDINATE FINAL

LOCATION WITH TENANT REP. SEE DETAIL 3F/A11.1 & 5A/A11.1. (SEE ELECTRICAL SHEETS).

- 18 REFRIGERATOR PROVIDED & INSTALLED BY TENANT (SEE ELECTRICAL SHEETS). 19 ICE MACHINE WITH DISPENSER PROVIDED AND INSTALLED BY TENANT. GC TO PROVIDE WATER, FLOOR SINK, POWER, AND SEWER. (SEE PLUMBING & ELECTRICAL SHEETS).
- 20 COFFEE VENDING MACHINE BY TENANT. GC TO PROVIDE WATER AND POWER. (SEE PLUMBING AND ELECTRICAL SHEETS) 21 METAL COAT RACKS PROVIDED TENANT & INSTALLED BY GC - SEE DETAIL 2E/A2.06.

22 AUTO OPERATOR FOR ADA, PROVIDE CONDUIT FOR DOOR OPENER.

- 23 COLUMNS & BRACING FOR OPERABLE PARTITION. (SEE STRUCTURAL SHEETS) 24 STEEL ROOF ACCESS LADDER WITH LADDER-UP SAFETY POST AND ROOF HATCH ABOVE WITH SAFETY RAILING SYSTEM - SEE DETAIL 3B/A9.6.
- 25 STAND ALONE UNISTRUT FRAME PLEXIGLASS BARRIER. 5MM (MIN.) PLEXIGLASS TO SPAN FROM BOTTOM OF COUNTERTOP TO 7'-0" A.F.F. BARRIER SHALL HAVE NO COVERAGE GAPS, INCLUDING AT ROUNDED COUNTERTOP CORNERS. PLEXIGLASS SHALL PROVIDE COVERAGE FOR ALL LEVELS OF THE COUNTER AND CORNERS.
- 26 UNDER COUNTER MOUNTED SINK (SEE PLUMBING SHEETS). 27 ACCESSIBLE HI-LO DRINKING FOUNTAINS. (SEE PLUMBING AND ELECTRICAL SHEETS)
- 28 JANITOR MOP / FLOOR SINK. PROVIDE 48"H F.R.P. PANELS TO 48" ON ALL WALLS, U.N.O. (SEE PLUMBING 29 VINYL BASE TO WRAP WALL MINIMUM WIDTH OF FLOOR TRANSITION RAMP & CORNER GUARD. START TILE BASE AT EDGE OF FLOOR TRANSITION. CORNER GUARD TO START AT TOP OF VINYL BASE.
- 32 TOP OF FIRE EXTINGUISHER HANDLE TO BE MOUNTED AT 48" MAX. A.F.F. INSTALL PER ANSI A117.1 308 & 309. 33 IN FLOOR POWER / DATA BOX. COORDINATE LOCATION WITH TENANT FURNITURE. SEE ELECTRICAL DRAWINGS. 46 TRASH/RECYLING BIN, OFOI.

47 8'-2" HIGH GALVANIZED DRIVER'S CAGE WITH MAIL SLOT AND CEILING.

- 48 FIRE EXTINGUISHER MOUNTED TO WALL 49 SURFACE MOUNTED BOLLARD - SEE DETAIL 4A/A11.1 51 GALVANIZED CHAIN LINK FENCE ENCLOSURE CEILING AT 8'-2" HEIGHT TO BE PROVIDED AND INSTALLED BY GC. PROVIDE DOORBELL ON EXTERIOR SIDE - TYP.
- 52 INTERCOM AT VESTIBULE TO RING AT SECURITY DESK. 53 KNOX BOX

54 PRE-ENGINEERED CANOPY

55 WIRE MESH PARTITION TO GO UP TO WITHIN AN INCH OR TWO OF THE BOTTOM OF THE CANOPY. INSTALL PER MANUFACTURER'S RECOMMENDATIONS. 57 PROVIDE 5' x 5' CONCRETE PAD AT EXT. BREAK ROOM

- 61 FOOTWASH STATION, REFER TO DETAIL 2A/CP3.2 FOR MOUNTING HEIGHTS. 62 1-1/2" BARRIER BAR - MIN. 20" EXTENSION FROM WALL - VERIFY EXCEEDS OUTERMOST EDGE OF DRINKING FOUNTAIN. (SEE DETAIL 4B/A11.1)
- 63 18" HIGH BENCH AFFIXED TO ADJACENT WALLS AND FLOOR. ALLOWABLE STRESS OF BENCH SHALL NOT BE EXCEEDED FOR MATERIALS USED WHEN A VERTICAL OR HORIZONTAL FORCE OF 250 LBS IS APPLIED AT ANY
- POINT ON THE SEAT, FASTENER, MOUNTING DEVICE, OR SUPPORTING STRUCTURE. REFER TO DETAIL 2E/A2. 64 BABY CHANGING STATION
- 66 FLOOR DRAIN (SEE PLUMBING SHEETS) 67 PROVIDE SEALENT AT FLOOR JOINTS AT PANEL OPENINGS 68 LOCATION OF TENANT PROVIDED AND GC INSTALLED ADA LOCKERS, MIN. 5% OF TOTAL. SEE DETAIL 3E/A2.06 69 LOCATION OF TENANT PROVIDED ADA COAT RACK, CONTRACTOR TO INSTALL. SEE DETAIL 2E/A2.06.

71 VAPOR MITIGATION SYSTEM RISER, COORDINATE WITH ROOF DRAINS - REFER TO VMS DRAWINGS

70 DEMARC ROOM FIRE EXTINGUISHER - SEE SPECIFICATIONS

KEY PLAN

25-24107-00 MAIN OFFICE AREA FLOOR

PLAN - WEST

PERMIT SET

05.13.2024 REVISIONS